



Replacement of Judd Road Bridge Over Mill River
Addendum #1

Mandatory Site visit will take place the project location, Judd Road Bridge over Mill River, on Thursday 5/1/2025 @ 2 PM.

See attached Schedule of Prices form for quantities and bid for contract items.

**TOWN OF MONROE & EASTON
SCHEDULE OF PRICES
FOR THE CONSTRUCTION OF**

**REPLACEMENT OF BRIDGE NO. 04929
JUDD ROAD OVER MILL RIVER
IN THE TOWN OF MONROE & EASTON**

DATE OF
BID SSUBMISSION

May 19, 2025

TIME: 2:00 P.M.

NO BIDS WILL BE ACCEPTED AFTER 2:00 P.M. "NO EXCEPTIONS"

Note: The bidder shall fill in, under the column "Unit Prices Bid," the unit prices, written in words and in numbers, for which he proposes to perform the various items of work called for, and under the column headed "Amount," the amount of each of the items at the unit price bid. After the proposal is opened and read, the quantities will be extended and totaled in accordance with the written bid prices and the bid will be verified or corrected.

Item Number		Items	Unit	Approximate Quantities	Unit Prices Bid		Amount (Figures)
					Figures	Writing	
0201001		Clearing and Grubbing	L.S.	1			
0202000		Earth Excavation	C.Y.	460			
0202200		Channel Excavation - Earth	C.Y.	20			
0202216	A	Excavation and Reuse of Existing Channel Bottom Material	C.Y.	10			
0202529		Cut Bituminous Concrete Pavement	L.F.	50			
0203202		Structure Excavation-Earth (excluding Cofferdam and Dewatering)	C.Y.	275			
0204151	A	Handling Water	L.S.	1			
0209001		Formation of Subgrade	S.Y.	390			
0212000		Subbase	C.Y.	110			
0213100		Granular Fill	C.Y.	25			
0216000		Pervious Structure Backfill	C.Y.	110			
0219001		Sedimentation Control System	L.F.	415			
0305001		Processed Aggregate	C.Y.	20			
0406170		HMA S1	Ton	140			
0406171		HMA S0.5	Ton	125			
0406173		HMA S0.25	Ton	15			
0406194	A	Joint And Crack Sealing of Bituminous Concrete Pavement	L.F.	50			
0406236		Material for Tack Coat	Gal.	140			
0406303	A	Sawing and Sealing Joints	L.F.	55			
0406312	A	Gutter Line Sealing for Bridges	L.F.	110			
0503001		Removal of Superstructure	L.S.	1			
0514201		Prestressed Deck Units (3'-0" x 1'-0")	L.F.	38			
0514217		Prestressed Deck Units (4'-0" x 1'-0")	L.F.	228			
0520036	A	Asphaltic Plug Expansion Joint System	C.F.	25			
0521001		Elastomeric Bearing Pads	C.I.	8316			
0601062		Footing Concrete	C.Y.	5			
0601064		Abutment and Wall Concrete	C.Y.	70			
0601088	A	Concrete Form Liners	S.F.	230			
0601118		Bridge Deck Concrete	C.Y.	30			
0601121		Parapet Concrete	L.F.	110			
0601123		Approach Slab Concrete	C.Y.	40			
0601504		1" Preformed Expansion Joint Filler for Bridges	S.F.	35			
0602030		Deformed Steel Bars-Galvanized	Lbs.	22900			
0703011	A	Intermediate Riprap	C.Y.	20			

**TOWN OF MONROE & EASTON
SCHEDULE OF PRICES
FOR THE CONSTRUCTION OF**

**REPLACEMENT OF BRIDGE NO. 04929
JUDD ROAD OVER MILL RIVER
IN THE TOWN OF MONROE & EASTON**

DATE OF
BID SSUBMISSION

May 19, 2025

TIME: 2:00 P.M.

NO BIDS WILL BE ACCEPTED AFTER 2:00 P.M. "NO EXCEPTIONS"

Note: The bidder shall fill in, under the column "Unit Prices Bid," the unit prices, written in words and in numbers, for which he proposes to perform the various items of work called for, and under the column headed "Amount," the amount of each of the items at the unit price bid. After the proposal is opened and read, the quantities will be extended and totaled in accordance with the written bid prices and the bid will be verified or corrected.

0706001		Micropiles	Ea.	14			
0706002		Verification Test for Micropiles	Ea.	2			
0706003		Proof Test for Micropiles	Ea.	2			
0706004		Micropile Length Adjustment	L.F.	60			
0707009	A	Membrane Waterproofing (Cold Liquid Elastomeric)	S.Y.	205			
0708001		Dampproofing	S.Y.	65			
0819002	A	Penetrating Sealer Protective Compound	S.Y.	40			
0822100.01		Temporary Traffic Barrier	L.F.	40			
0904051	A	3 Tube Curb Mounted Bridge Rail	L.F.	85			
0910030		Thrie Beam Bridge Attachment	Ea.	4			
0910300		Metal Beam Rail (R-B MASH)	L.F.	55			
0911924		R-B End Anchorage - Type II	Ea.	4			
0944000		Furnishing and Placing Topsoil	S.Y.	380			
0950005		Turf Establishment	S.Y.	380			
0969060	A	Construction Field Office (Small)	Mo.	9			
0970006		Trafficperson (Municipal Police Officer)(estimated cost)	Est.	1	\$8,000.00	EIGHT THOUSAND DOLLARS & ZERO CENTS	
0970007		Trafficperson (Uniformed Flagger)	Hr.	80			
0971001	A	Maintenance and Protection of Traffic	L.S.	1			
0974001		Removal of Existing Masonry	C.Y.	110			
0975004		Mobilization and Project Closeout	L.S.	1			
0976002		Barricade Warning Light-High Intensity	Day	1080			
0977001		Traffic Cone	Ea.	20			
0979003		Construction Barricade Type III	Ea.	4			
0980020		Construction Surveying	L.S.	1			
1205216		Type DE-7C Delineator	Ea.	6			
1208931		Sign Face - Sheet Aluminum (Type IX Retroreflective Sheeting)	S.F.	5			
1210102		4" Yellow Epoxy Resin Pavement Marking	L.F.	420			
1220027		Construction Signs	S.F.	215			

Kindly insert here the total amount of your Bid \$ _____

It is understood that the unit prices shall govern in case of discrepancy between the unit-prices and this amount.

This bid includes addenda no.: _____